

MODEL : PLC-30-15

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1 : 2.6 Vp-p (Max)	I/P : 230VAC O/P : 100% LOAD Ta : 25°C	V1 : 2.04 Vp-p (Max)	P
2	OUTPUT VOLTAGE ADJUST RANGE	CH1 : 14.25 V- 16.5 V	I/P : 230 VAC I/P : 115 VAC O/P : MIN LOAD Ta : 25°C	13.02 V- 17.65 V / 230 VAC 13.02 V- 17.65 V / 115 VAC	P
3	OUTPUT CURRENT ADJUST RANGE	CH1 : 1.5 A-2.06A	I/P : 230 VAC I/P : 115 VAC Ta : 25°C	1.26 A- 2.37 A / 230 VAC 1.26 A- 2.37 A / 115 VAC	P
4	OUTPUT VOLTAGE TOLERANCE	V1 : 10 %- -10 % (Max)	I/P : 100 VAC / 264 VAC O/P : 100% LOAD / MIN LOAD Ta : 25°C	V1 : 0.7 %- -0.7 %	P
5	LINE REGULATION	V1 : 3 %- -3 % (Max)	I/P : 100VAC ~ 264 VAC O/P : 100% LOAD Ta : 25°C	V1 : 0.12 %- -0.12 %	P
6	LOAD REGULATION	V1 : 5%- -5 % (Max)	I/P : 230 VAC O/P : 100% LOAD -MIN LOAD Ta : 25°C	V1 : 0.25 %- -0.25 %	P
7	SET UP TIME	230VAC : 500 ms (Max) 115 VAC : 3000 ms (Max)	I/P : 230 VAC I/P : 115 VAC O/P : 100% LOAD Ta : 25°C	230VAC/ 443.232 ms 115VAC/ 410.589 ms	P
8	OVER/UNDERSHOOT TEST	< ±10%	I/P : 230 VAC O/P : 100% LOAD Ta : 25°C	TEST : <10 %	P

## INPUT FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	90VAC~264 VAC	I/P : TESTING O/P : 100% LOAD Ta : 25°C	76 V~264V	P
			I/P : LOW-LINE-3V= 87V HIGH-LINE+15%= 300V O/P : 100% LOAD /MIN LOAD ON : 30 Sec. OFF : 30 Sec 10MIN ( AC POWER ON/OFF NO DAMAGE )	TEST : OK	
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE OSC	I/P : 90 VAC ~ 264 VAC O/P : 100% LOAD ~MIN LOAD Ta : 25°C	TEST : OK	P
3	POWER FACTOR	0.90 / 230 VAC(TYP) 0.90 / 115 VAC(TYP) ≥0.9 at 75 ~ 100% load	I/P : 230 VAC I/P : 115 VAC O/P : 100% LOAD Ta : 25°C	PF= 0.92 / 230 VAC PF= 0.98 / 115 VAC ≥0.9 at 75 ~ 100% load	P
4	EFFICIENCY	83.5% (TYP)	I/P : 230 VAC O/P : 100% LOAD Ta : 25°C	85.9 %	P
5	INPUT CURRENT	230V/ 0.2 A (TYP) 115V/ 0.4 A (TYP)	I/P : 230 VAC I/P : 115 VAC O/P : 100% LOAD Ta : 25°C	I = 0.17 A/ 230 VAC I = 0.31 A/ 115 VAC	P
6	INRUSH CURRENT	230V/ 35 A (TYP)  COLD START	I/P : 230 VAC O/P : 100% LOAD Ta : 25°C	I = 32 A/ 230 VAC	P
7	LEAKAGE CURRENT	< 0.5 mA / 240 VAC	I/P : 264 VAC O/P : Min LOAD Ta : 25°C	L-FG : 0.001 mA N-FG : 0.001 mA	P

## PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	100 %~ 110 %	I/P : 230 VAC I/P : 115 VAC O/P : TESTING Ta : 25°C	105 %/ 230 VAC 105 %/ 115 VAC Constant Current Limiting	P
2	OVER VOLTAGE PROTECTION	CH1 : 17 V- 22 V	I/P : 230 VAC I/P : 115 VAC O/P : MIN LOAD Ta : 25°C	20.7 V/ 230 VAC 20.7 V/ 115 VAC Shunt down Re- power ON	P
3	OVER TEMPERATURE PROTECTION	SPEC : TSW1 : 95 ± 10°C O.T.P NO DAMAGE	I/P : 230 VAC O/P : 100% LOAD	O.T.P Active Shunt down Re-power ON	P
4	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P : 264 VAC O/P : 100% LOAD Ta : 25°C	NO DAMAGE Hiccup Mode	P

## ENVIRONMENT TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	TEMPERATURE RISE TEST	MODEL : PLC-30-9 1. ROOM AMBIENT BURN-IN : 17 HRS I/P : 230VAC O/P : 100% LOAD Ta= 24.7°C 2. HIGH AMBIENT BURN-IN : 1 HRS I/P : 230VAC O/P : 100% LOAD Ta= 40.8 °C			P
2	OVER LOAD BURN-IN TEST	NO DAMAGE 1 HOUR ( MIN )	I/P : 230 VAC O/P : 115 % LOAD Ta : 25°C	TEST : OK	P
3	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P : 230 VAC O/P : 100 % LOAD Ta= -30 °C	TEST : OK	P
4	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 40°C NO DAMAGE	I/P : 272 VAC O/P : 100% LOAD Ta= 40°C HUMIDITY= 95 %R.H	TEST : OK	P
5	TEMPERATURE COEFFICIENT	± 0.06 %(0-50°C)	I/P : 230 VAC O/P : 100% LOAD	± 0.03 %(0-50°C)	P
6	VIBRATION TEST	1 Carton & 1 Set (1) Waveform : Sine Wave (2) Frequency : 10-500Hz (3) Time : 72min (4) Acceleration : 2G (5) Test Time : 1 hour in each axis (X.Y.Z) (6) Ta : 25°C		TEST : OK	P

### SAFETY TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P : 3.75KVAC/min	I/P-O/P : 4.2KVAC/min Ta : 25°C	I/P-O/P : 2.16 mA  NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P : 500VDC>100MΩ	I/P-O/P : 500 VDC Ta : 25°C /70% RH	I/P-O/P : 25 GΩ  NO DAMAGE	P
3	APPROVAL	TUV : Certificate NO : R50103804 UL : File NO : E186843			P

### E.M.C TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2 CLASS A CLASS C CLASS D	I/P : 230 VAC/50HZ O/P : 100% LOAD/70%LOAD Ta : 25°C	PASS	P
2	CONDUCTION	EN55015 CLASS B	I/P : 230 VAC (50HZ) O/P : 100% LOAD /50% LOAD Ta : 25°C	PASS Test by certified Lab	P
3	RADIATION	EN55015 CLASS B	I/P : 230 VAC (50HZ) O/P : 100% LOAD Ta : 25°C	PASS Test by certified Lab	P
4	E.S.D	EN61000-4-2 LIGHT INDUSTRY AIR : 8KV / Contact : 4KV	I/P : 230 VAC/50HZ O/P : 100% LOAD Ta : 25°C	CRITERIA A	P
5	E.F.T	EN61000-4-4 LIGHT INDUSTRY INPUT : 1KV	I/P : 230 VAC/50HZ O/P : 100% LOAD Ta : 25°C	CRITERIA A	P
6	SURGE	IEC61000-4-5 LIGHT INDUSTRY L-N : 1KV	I/P : 230 VAC/50HZ O/P : 100% LOAD Ta : 25°C	CRITERIA A	P
7	Test by certified Lab & Test Report Prepare				

### M.T.B.F & LIFE CYCLE CALCULATION

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	CAPACITOR LIFE CYCLE	PLC-30-9 : SUPPOSE C 106 IS THE MOST CRITICAL COMPONENT I/P : 230VAC O/P : 100% LOAD Ta= 25 °C LIFE TIME= 53282 HRS I/P : 230VAC O/P : 100% LOAD Ta= 50 °C LIFE TIME= 28012 HRS			P
2	MTBF	MIL-HDBK-217F NOTICES2 PARTS COUNT TOTAL FAILURE RATE : 621.4K HRS			P
3	DMTBF/Accelerated Life Test	Demonstration Mean Time Between Failure(Expected Life) : 20,000 hours @ Tcase 80°C; 50,000 hours @ Tcase 65°C			P

### COMPONENT STRESS TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor ( D to S) or (C to E) Peak Voltage	Q1 Rated STP9NK70ZFP : 700V 7.5A	I/P : High-Line +3V = 267 V O/P : (1) 100% LOAD Turn on (2) Output Short Ta : 25°C	(1) 600 V (2) 444 V	P
2	Diode Peak Voltage	D100 Rated FME220A : 100V 20A	I/P : High-Line +3V = 267 V O/P : (1) 100% LOAD Turn on (2)Output Short Ta : 25°C	(1) 82 V (2) 67 V	P
3	Clamp Diode Peak Voltage	D2 Rated IN4007 : 1000V 1A	I/P : High-Line +3V = 267 V O/P : (1) Dynamic Load 90%Duty/1KHz Ta : 25°C	(1) 392 V	P
4	Control IC Voltage Test	U1 Rated TDA4863G : 22V	I/P : High-Line +3V = 267 V O/P : (1) 100% LOAD Turn on /Off (2) Min load Turn on /Off (3) 100% /Min load Change Ta : 25°C	(1) 14.5 V (2) 14.5 V (3) 14.5 V	P

DATE	SAMPLE	TEST RESULT	TESTER	APPROVAL
2009/6/16	W0905C35	PASS	SANFORD SU	VINCENT TSENG

2003/12/12 A50-F023